

zał. 5 elementy trasy ze współrzędnymi

-----  
 Elementy trasy (wersja skrócona)  
 -----

Projekt :  
 Plik :D:\PRACA OD 09.12.2016\PZD Siemiatycze - dr. pow. wólka  
 Zamkowa-Runice-Minczewo\TRASA 11.ułc  
 Utworzony : data: 2017-06-08 godz. 12:08:51

ELEMENT	OD	DO		
	(X = 5810822,360;Y = 8404685,310)			
Prosta	1+200,00	1+222,05	L=22,05m	
Łuk kołowy	1+222,05	1+289,17	L=67,11m	R=250,00m
	W1 (X = 5810878,170;Y = 8404686,000)			
Prosta	1+289,17	1+421,29	L=132,12m	
Łuk kołowy	1+421,29	1+470,16	L=48,87m	R=700,00m
	W2 (X = 5811062,290;Y = 8404637,790)			
Prosta	1+470,16	1+539,29	L=69,13m	
	W3 (X = 5811150,940;Y = 8404607,830)			
Prosta	1+539,29	1+627,35	L=88,06m	
Łuk kołowy	1+627,35	1+669,88	L=42,53m	R=200,00m
	W4 (X = 5811254,630;Y = 8404572,930)			
Prosta	1+669,88	2+028,24	L=358,35m	
	W5 (X = 5811631,950;Y = 8404530,490)			
Prosta	2+028,24	2+196,25	L=168,01m	
	W6 (X = 5811798,930;Y = 8404511,900)			
Prosta	2+196,25	2+328,74	L=132,50m	
	W7 (X = 5811930,570;Y = 8404496,860)			
Prosta	2+328,74	2+419,39	L=90,65m	
	W8 (X = 5812020,680;Y = 8404487,000)			
Prosta	2+419,39	2+500,56	L=81,17m	
	W9 (X = 5812101,270;Y = 8404477,330)			
Prosta	2+500,56	2+563,00	L=62,44m	
	W10 (X = 5812163,310;Y = 8404470,300)			
Prosta	2+563,00	2+583,00	L=20,00m	
	W11 (X = 5812183,150;Y = 8404467,750)			
Prosta	2+583,00	2+626,21	L=43,21m	
	W12 (X = 5812226,090;Y = 8404462,940)			